



# Collaborative Value-engineering Management in

Happy Valley Underground Stormwater Storage Scheme



LUK Wai-hung Drainage Services Department





#### **Contents**


- Project Background
- Collaborative Value-engineering Management (CVM)
  - Team Building
  - Value Engineering
  - Risk and Programme Management
- Trust and Morale Ups and Downs
- **■**Conclusion





# Project Background

#### THE PROBLEM - FLOODING



Percival Street




Queen's Road East



Happy Valley Recreation Ground and Race Course



#### THE CONCERN



E

#### THE PROJECT- HVUSSS



#### THE CONTRACT



Contract No.	DC/2012/03					
<b>Contract Name</b>	Happy Valley Underground Stormwater Storage Scheme					
Employer	Drainage Services Department					
PM/Supervisor	Chief Engineer/DPD, DSD					
Scope of Works	Construction of storage tank, box culvert, pump house					
<b>Original Target Cost</b>	HK\$ 678M					
Duration	Sep 2012 – April 2018 (64 months)					
NEC3 Option	Option C – Target contract with activity schedule					
Contractor	Chun Wo Construction & Engineering Co. Ltd.					
QS Consultant	Mott MacDonald Hong Kong Limited					
NEC Advisor	Arcadis / JCP					





#### **NEC3 Cl. 10.1:**

# Mutual Trust and Cooperation

among
Employer,
Project Manager,
Supervisor, Contractor,....








Employer
Project Manager
Supervisor
Contractor
Sub-contractor
Stakeholders
Consultants

••••







#### NEC3:

Risk Management
Programme Management
Compensation Events
Open Book Account





360° Communication
Active Subcontractor Management




# Collaborative Value-engineering Management



# Collaborative Value-engineering Management (CVM) in HVUSSS





Click to show Video...







# In CVM, we develop mutual trust and cooperation by 360° communication network




## **Team Building**



#### **360° Communication Network**

36
WhatsApp
Groups
in different
categories





# Stakeholders Workshop

District Council members, HKJC, LCSD, Contractor, Subcontractors...





# **Team Building**



#### 360° Communication Network









Project Manager's Staff








#### **360° Communication Network**

Drainage Services Department Drainage Projects Division



ChunWo Construction & Engineering Co. Ltd.

Contract No. DC/2012/03 - Happy Valley Underground Stormwater Storage Scheme
Organisation Chart for Joint Project Manager / Contractor Site Office





Joint Organization Chart






# In CVM, we promote value-engineering by utilizing tools in NEC Contract





#### Pain/ Gain Share by Open Book Account


**Initiative for Contractor to propose Cost-saving Design** 







#### Pain/ Gain Share by Open Book Account




Cost Saving Design: Cut-off Wall / Sub-surface Drainage System





#### **Timely Assessment of Compensation Event**

CE about Water Harvesting System was issued within one month with no abortive works







#### **Active Subcontractor Management**

#### **Concerns on Target Contract:**

- ? Cost of work by subcontractor is reimbursable
- ? Contractor may have no incentive to selective most competitive offer

#### **Control Measures on**

- ➤ Subcontract Package
- **≻**Selection
- **≻**Payment
- **≻**Finalisation







#### **Active Subcontractor Management**






#### **Tender Briefing**



#### **Tender Interview**

#### Sum of awarded subcontracts



No. of finalized Subcontracts = 28 out of 126



# WIN NED WIN

#### **Active Subcontractor Management**



#### **Alternative Turf Proposal**

Save **\$3M** out of \$16M



Advance Progress by

1 month

**Capture Innovative Proposal by Subcontractor** 





# In CVM, we manage risk and programme by utilizing tools in NEC Contract





#### **Early Warning and Risk Register**

#### Pre contract: 9

- Ground Condition
- Excessive Settlement
- Congested Working Environment
- Flood Risk

#### Construction: 44


- Interfacing works with HKJC
- Delay in Access Date of Pitch No. 4
- Lack of engineering and site resources
- Slow progress of different work fronts
- Missing details
- Defects







#### **Early Warning and Risk Register**







#### **Collaboration in Risk and Programme Management**

Interface construction works of HKJC and DSD during summer break of 2014






**Tight Schedule, High Project Risk** 





#### **Collaboration in Risk and Programme Management**












#### **Collaboration in Risk and Programme Management**







#### **Collaboration in Risk and Programme Management**


**Construction of Pipe Pile Wall at Crescent Garden** 








#### **Collaboration in Risk and Programme Management**



Shared ELS system









#### **Collaboration in Risk and Programme Management**

#### **Shared Access**







#### **Collaboration in Risk and Programme Management**









# Trust and Morale – Ups and Downs






# **Trust: Ups and Down**



#### Contract DC/2012/03

Happy Valley Underground Stormwater Storage Scheme

Partnering Evaluation Scoring for Targets in Progress, Safety, Communication and Cooperation
Frontline Staff



Frontline Staff	Oct-Nov 13	Dec13-Jan 14	Feb-Mar 14	Apr-May 14	Jun-Jul 14	Aug-Sep 14	Oct- Nov 14		Feb-Mar 15
DSD	3.79	3.68	3.85	3.89	4.18	4.13	4.09	4.09	4.06
Chun Wo	3.17	2.83	3.53	3.37	3.44	3.51	3.52	3.56	3.58







# **One Team One Goal**






# **Achievement**



#### **Highly Commended New Engineering Contract (NEC) Large Project** of the Year 2015 Award by NEC Users' Group in UK



(photo taken at the prize presentation ceremony held in London, UK, April 2015)



## Conclusion



ACHIEVEMENTS in progress, cost, quality and safety
CERTAINITY of risks about time and cost for all parties
TRUST has to be earned
EFFORT has to be paid for the achievements







